

Bid # 26-046 **Project:** Sanitary Sewer Comminutors
Date: 9/24/2026 **Time:** 2:00pm **Department:** PW

Bidder Name		Municipal Equipment Company, Inc	/	/	/
Bidder #		1			
No	Description	Unit	Price per Unit		
1	Peruque – Open Channel Comminutor – Heavy Duty Body Housing; Cantilevered Drive Design; Mechanical Seal; Hardened Stainless Steel Stationary And Rotary Cutters; Heavy Duty Sizing Screen – Stainless Steel; Painted 2 Coats Heavy Epoxy Coating – OSHA Blue	Each	\$64,257		
2	Peruque – Submersible Drive And Motor With Full Submersible Capability; 3 HP Submersible Explosion Proof, 230/460V. 3ph, 60 Hz. Motor; 50 Feet Of Cable; Sealed Gear Reducer - Vertical - Oil Filled	Each	\$20,418		
3	Peruque – Automatic Reversing Controller - Nema 4X FRP Enclosure; PLC Logic Control, IEC Starters; LED Indicators - For Long Life; Current Sensing Auto-Reversing Program	Each	\$5,920		
4	Peruque – Guide Plate - Plate Frame Mounted To Grinder; 304 Stainless Steel; To Mate Up To Existing Guide Rails	Each	\$3,830		
5	Peruque – OVERFLOW BAR SCREEN; 1/4 X 2" X 24" Tall T304SS BAR; Welded Construction; Mounting System	Each	\$10,745		

6	Peruque – Rigid Lifting Bail - 304 Stainless Steel; Angle Stock	Each	\$4,590					
7	Peruque – Spare Parts - Set of rotary cutters and hardware; Set of stationary cutters and hardware; One mechanical seal; Three (3) fuses of each size; Three (3) LED lamps of each size and color	Each	\$13,020					
8	West – Open Channel Comminutor -Heavy-Duty Body Housing - Ductile Iron; Cantilevered Drive Design; Mechanical Seal -Located Above Cutters; Stationary And Rotary Cutters - Hardened SS; Heavy-Duty Sizing Screen - Mounted In Multiple Sections; Painted 2 Coats Heavy Epoxy Coating - Osha Blue	Each	\$132,445					
9	West – 5hp Submersible Drive - 5hp 230/460v. 60 Hz (Ip68) Explosion-Proof Submersible Motor; Gear Reducer - Cycloidal , Quill Type -Sealed Housing; Oil Lubricated For Long Life; 50 Ft. Cable Length	Each	\$25,135					
10	West – Automatic Reversing Controller - Nema 4X FRP Enclosure; PLC Logic Control, IEC Starters; LED Indicators - For Long Life; Current Sensing Auto-Reversing Program	Each	\$5,920					
11	West – Guide Plate - 304SS - Plate Frame Mounted To Grinder; Constructed In 304 SS; To Mate Up To Existing Guide Rails	Each	\$3,830					
12	West – Overflow Bar Screen - 30" Long, X 2" 316ss Bar; Welded Construction; Mounting System	Each	\$13,108					

13	West – Rigid Lifting Bail - 304 Stainless Steel Construction; Rigid Lifting Mechanism	Each	\$5,107				
14	West – Spare Parts - Set of rotary cutters and hardware; Set of stationary cutters and hardware; One mechanical seal; Three (3) fuses of each size; Three (3) LED lamps of each size and color	Each	\$30,800				
15	Startup Assistance – 2 (Two) Days and 2 (Two) Trips	Each	\$5,920				
Total			\$41,027				

Prepared by: Gautam Muresi, Purchasing Agent